

Cements

All Weather – “Quick-Set” Cement



Recommended pipe application and sizes	Set-up time (Evaporation Rate)	Recommended installation temperature	Lap Shear @ 23°C	Viscosity at 24°C as manufactured
Recommended for all grades and types of Carlton PVC conduit, duct, wireway and fittings, except Flex-Plus® Blue™ ENT (Electrical Nonmetallic Tubing.) Up through 6 in. diameter.	-20 to -12°C 6-8 minutes -12 to -1°C 4-5 minutes -1 to 10°C 3-4 minutes 10 to 21°C 1-2 minutes 21 to 32°C 1/2-1 1/2 minutes	-20 to 37.7°C	2 hrs. 350 psi 16 hrs. 800 psi 72 hrs. 1,500 psi	400-700 cps

Cat. No.	Size	Applicator	Ctn. Qty.	Ctn. Wt. (lb.)
VC9983C	473 ml	Dauber	24	30.0
VC9985C	118 ml			7.5

Meets ASTM D-2564